



Bow Concord I-93 Improvements T-A000(018) 13742


Joint Public Workshop

June 26, 2019






Project Overview








I-93 Typical Sections







Project Goals



- Red List Bridges
- Address Geometric Issues
- Address Operational Issues
- Maintain Access

- Pedestrian/Bicycle Accommodation
- Provide Stormwater Treatment
- Minimize Resource Impacts
- Minimize Property Impacts





Recommended Preferred Alternative



I-89 Area Concept K Exit 12 Area Concept F

Exit 13 Area Concept B

Exit 14/15 Area Concept F2






Exit 14/15 Area







Exit 14 / 15 Area - Proposed







Exit 15 - Proposed

- Cloverstack
- Eliminates 2 Loop ramps
- Eliminates 4 weaves
- Maintains all Access







Exit 14 - Proposed




- Modified Diamond
- Eliminates Northbound Entrance Ramp
- Easterly shift of I-93


- Maintains access to Stickney Ave
- Avoids Historic Buildings
- Avoids Unitil Sub-station
- Avoids Railroad corridor





Exit 14 - Proposed









Concord Comments/Concerns

- 1. Clear brush along I-93
- 2. Remove Highway Garage complex on Stickney Avenue
- 3. Consistency with Concord's Vision for I-93
- 4. Pedestrian Access from Downtown to the Merrimack River
- 5. Increased Traffic on Fort Eddy Road
- 6. Loss of the Northbound Entrance ramp at Exit 14





Concord Comments/Concerns

1. Clear brush along I-93


City is coordinating with Bureau of Turnpikes to get permission for the City to do the clearing.

2. Remove Highway Garage complex on Stickney Avenue

Separate project and not associated with Bow Concord. Funded through the State budget.








- Functionally identical to Concept F2
- Loudon Road over I-93
- Relocation of Railroad possible
- Access to Ralph Pill via Stickney Ave.
- Additional \$41M

- Impacts Include:
 - √ 16-20 Month closure of Loudon Road (carries 20,000+ vehicles per day)
 - ✓ Short term closure of Exit 14 NB Off Ramp
 - Long term closure of both Exit 14 SB Ramps
 - ✓ Utilities under Loudon Road








- Relocate Railroad East close to I-93
- Access to Ralph Pill via Storrs Street
- Additional \$19.2M

- Railroad Relocation Impacts include:
 - Unitil Substation
 - Historic Building
 - Bus Depot












EXITS 14/15 AREAS CONCEPT F3




Loudon Road Profile






EXITS 14/15 AREAS
CONCEPT F3








Utilities








4. Pedestrian Access from Downtown to the Merrimack River







4. Pedestrian Access from Downtown to the Merrimack River




Note: Pedestrian could be lowered about 3' for Concept F3.





4. Pedestrian Access from Downtown to the Merrimack River

Pedestrian Bridge - Option 2



Note: Pedestrian could be lowered about 4' for Concept F3.






5. <u>Increased Traffic on Fort Eddy Road</u>


Design Year 2035

6. Loss of the Northbound Entrance ramp at Exit 14


































Project Costs Bow Concord I-93 Improvements Project

Preferred Alternative Cost Matrix (Millions \$)

SEGMENT	Concept	Construction \$	Right-of-Way \$	Engineering and Permitting \$	Mitigation \$	Utility \$	Total Project \$
I-89 Area	К	\$62.0	\$1.16	\$6.20	\$0.62	\$0.00	\$70.0
Exit 12	F	\$29.5	\$0.09	\$2.95	\$0.30	\$1.00	\$33.9
Exit 13	В	\$34.8	\$0.36	\$3.48	\$0.35	\$0.00	\$39.0
Exit 14/15	F2	\$111.2	\$0.47	\$11.12	\$1.11	\$1.00	\$125.0
Total		\$237.5	\$2.1	\$23.8	\$2.4	\$2.0	\$267.9





Potential Costs

SEGMENT	Concept	Construction \$	Right-of-Way \$	Engineering and Permitting \$	Mitigation \$	Utility \$	Total Project \$
Exit 14/15	F2	\$111.2	\$0.47	\$11.12	\$1.11	\$1.00	\$125.0
Exit 14/15	F3	\$148.1	\$0.47	\$14.81	\$1.48	\$1.00 [*]	\$165.9 + \$40 .9
Exit 14/15	F3 with Railroad Relocation	\$153.2	\$5.09	\$15.32	\$1.53	\$10.00	\$185.1 +\$60.1

*Does not include utility impacts/relocations on Loudon Road.

Pedestrian Bridge (Construction Only)

\$12M - \$30M





Open Discussion







Schedule

- Final Environmental Document Summer 2019
- Final Design / Right of Way Acquisition 2019 to 2023
- Construction Begin 2024 with current funding
- Completion 2033 or sooner









Questions

www.i93bowconcord.com

